

CHITALDRUG DIVISION.

Notice dated 2nd September 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 27th September 1930, for Restoring Malalkere (Sannakere tank) Register No. 39 of Davangere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Malalkere Tank (Sannakere) Register No. 39 of Davangere Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Restoring Malalkere Tank, Register No. 39 of Davangere Taluk.

No.	Item of work	Per	Quantity
<i>Bund R. L. 55.00.</i>			
1	Removing jungle over front and rear slopes	Lump	sum
2	Earthwork to bund including watering and tamping	C.yd.	3,810
3	Turfing the slopes of the bund	S.yd.	5,319
4	New stone revetment with jelly backing	C.yd.	517
5	Removing and fixing old grade stones and painting	Each	32
6	Providing new grade stones with ogiving and painting	"	5
7	Do new top width stones with painting	"	37
8	Do register No. stone	"	1
9	Do Gauge stones	"	2
10	Do B. M. stones	"	2
11	Do Constructive masonry stone	"	1
<i>Left Waste Weir R. L. 55.00.</i>			
1	Earthwork excavation	C.yd.	105
2	Removing and refixing masonry	"	6
3	New rough stone work	"	10
<i>Right Waste Weir R. L. 55.00.</i>			
1	Earthwork excavation	C.yd.	54
2	New rough stone work	"	46

R. TIPPAYIA,
Executive Engineer.

S. E.